

# COMCAST CABLE TRENCHING SPECIFICATIONS

Conduit sweeping up  
On a pole- Fig 1

Conduit shall be installed  
4" to 6" above dirt line  
And capped or tape off With  
Min 1/4" pull rope in place

DIRT LINE

24" x 2" x 90 Sweep

Trench profile- Fig 2

Dirt Line-Conduits shall  
be installed 4" to 6"  
above dirt line and  
capped or tape off.

DIRT LINE

24" x 2" x 90 Sweep

Conduit sweeping up  
On a pole- Fig 3

Comcast Trenching specifications for Crescent Ct. to Vine Hill Rd.

- All conduits shall be Schedule 40 PVC
- All joints must be glued with PVC Cement
- All Sweeps must be 2" x 24" x 90
- All risers shall be placed in appropriate quadrant
- All Conduits must have a minimum of 1/4" pull rope install.
- Contractor/Customer is required to call U.S.A. prior to digging for all locates.
- All Trenching and or Conduit must be inspected and approved by Comcast with 48hrs notice customer/contractor must meet 90% compaction or better and takes responsibility for any and all damages that may occur including future drainage issues, sinking, etc.
- Customer agrees by signature to release Comcast Cable of any liability if self installed and or own contractor.

Signature

Date

